

November 13, 2015

Subject: Brown County Jail, TX – CCTV System Upgrade

**Camera System**

MTS will provide and install a Pelco Digital Sentry CCTV system. The Digital Sentry system is IP based which allows for maximum flexibility and ease of expansion. MTS will provide two (2) Pelco DSSRV2-240 servers. Each server has 24TB of storage which will give the system a total of 48TB. This will allow storage of recording for 30 days at 50% activity rate. The DSSRV2 servers use a RAID 5 storage configuration which provides a fault tolerant solution.

Four (4) ENC5516-US encoders will be provided in order to connect the existing analog cameras to the new servers. The existing analog cameras will be connected to the ENC5516s. There are sixty four (64) existing fixed analog cameras which will be interfaced with the DSSRV2 servers.

MTS will reuse the existing sixty-four analog cameras as is. MTS will replace four (4) existing exterior PTZ cameras with Pelco S6220 2MP cameras. MTS will pull Cat6 cable to the four (4) new PTZ camera locations.

MTS will provide one (1) HP 22" monitor at the Central control station to serve as a spot monitor. The spot monitor will be capable of viewing up to four (4) cameras simultaneously with one (1) of the camera views being reserved for camera call ups based on alarms or intercom selections. MTS will install one (1) HP 2920-24-POE switch which will allow the facility to add POE enabled cameras in the future without having to add head end equipment.

The existing cameras, racks, cabling and power supplies will be reused as is except where otherwise noted.

**Pricing**

MTS is pleased to provide the above scope of work for a **total of \$50,600.**


**Warranty**

1. MTS provides the manufacturers standard warranty that all products are to be free of defects in material and workmanship for a period of one year from date of substantial completion.
2. Conditions of the warranty apply only to materials supplied as part of this quote.
3. MTS is not responsible for damage caused by Acts of God, neglect or abuse by others who have gained access to the equipment.

**Lead Times and Submittals:**

1. MTS will provide submittals within four (4) weeks of receipt of contract.
2. MTS will provide all necessary material within four (4) weeks of receipt of approved submittals.
3. MTS will complete installation within three (3) weeks of material arriving onsite.

January 19, 2016  
(Exhibit #3)



**Terms of Payment**

1. All pricing is good for 30 days from date of quote.
2. All invoices will be paid within 30 days from invoice date.
3. All invoices not paid within 30 days will be subject to a 1.5% per 30-day late charge.
4. All invoices not paid within 60 days will result in the account being put on Credit Hold.
5. A tax exemption certificate must be provided for each project. No sales tax has been included in the above price.

If I can be of any assistance or answer any questions, please do not hesitate to call me at 800-392-8292.

Sincerely,

*Michelle Gafford*