



Est. 1980

Kirby Cabler Enterprises General Contractors

119 East River Oaks • Early, Texas 76802

325-646-6125 • Cell: 325-647-7764 • Fax: 325-646-6310

www.kirbycabler.com

June 23, 2014

The following budget estimate is for an on-site waste water treatment facility located at Brown County Precinct Maintenance Barn May, Texas. This is a budget estimate only and includes the following;

- 1- 750 gallon, 2 compartment concrete settling tank
- 120'-4" Schedule 80 PVC
- 20' - 4" Schedule 40 PVC from tank downhill to drain field
- 60' - 36" Hancor Septic Panels
- 1 - Clean-out Set-up
- Price contingent on ideal soil conditions (class 111 soil)
- Pump Existing tank and fill
- Permit provided
- Material & Labor

Proposed Total**\$6,182.00****Note:**

- This is an estimate only not a firm bid
- This estimate price is only valid for 30 days after submittal
- All KCE laborers are covered by workers compensation
- All KCE laborers are drug screened and criminal back ground checked
- KCE General Contractors carries liability insurance of \$1/2 million
- KCE is bidding as the Primary Contractor

Thank You!

Kirby Cabler

August 4, 2014
(Exhibit # 7)