



COOD FENCES MAKE GOOD NEIGHBORS AND WE ARE THE SECURE CHOICE.

Address: 1017 West Commerce Brownwood, Texas 76801


Sheriff Office Concrete Quote

6' x 74'6" sidewalk, 4" thick, 3/8 rebar on 12". Cut out, haul-off and replace 6' x 12' of concrete. 447sq. ft.

5' x 18' sidewalk, 4" thick, 3/8 rebar on 12". 90 sq. ft.

price to include all labor and materials

Total \$4259.00







COOD FENCES MAKE GOOD NEIGHBORS AND WE ARE THE SECURE CHOICE.

Business address: 1017 West Commerce Brownwood, Texas 76801

Change Order

Brown County Sheriff Dept.

120' of 6' 9 gauge chain link + 3 strand barbed wire @ \$18.03 per foot = \$2163.60

120' of 18" razor tape @ \$4 per foot = \$480.00

2-5 ' walk gates @ \$300.00 ea = \$600.00

Total due \$3243.60

riple Submitted by Date

4, 2015 Accepted by___ Date

The above work will be completed in a professional manner for the amount shown. Payable at 50% down with the balance upon completion. Any alterations or deviation from above specifications will become an extra charge over the sum stated in this contract. I/We agree to the above listed proposal and authorize The Fence Guyz to start and complete the said proposal. I/We also agree to payments and terms stated in this proposal.

All material remain the property of The Fence Guyz until paid in full.

Customer is responsible for damage to underground lines. Cast iron products not warranted

1 Year Warranty