



RHS Construction Services, LLC

PROPOSAL

General Contractor:
 Jeff H
 Southwest Architects

Regarding:
 Brown County Jail
 Brownwood, TX

DATE : May 21, 2020

SCOPE OF WORK

Provide labor, material, and equipment for the following.

ACOUSTIC WALL PANELS

- Acoustic Wall Panels at one room sized 12'-8" X 8'-4"
- Panels to extend to 10' AFF
- Impact Resistant Panels with Square Hardened edges
- Guilford 2100 Fabric, Color TBD
- Z-Clip Mounting to CMU walls
- Freight to the site included
- Lead Time is Approx. 6-8 weeks depending on manufacturer work load

OPTION A - MATERIAL ONLY PROVIDED and SHIPPED TO SITE

-1-1/8" Thick Panels (1/8" is hardened surface) ----- **\$5,850.00**

OPTION B - MATERIAL ONLY PROVIDED and SHIPPED TO SITE


-2-1/8" Thick Panels (1/8" is hardened surface) ----- **\$6,734.00**

INSTALLATION LABOR

-Provide Labor and equipment to install either A OR B of the options listed above --- **\$1,028.00**

EXCLUSIONS

- TAXES
- Demo of any wall finishes
- Removal or Replacing of any MEP Items
- Painting of any type
- Night work or overtime wages (work to be performed during normal business hours)


 Garrett Poole 5-21-20
Date

June 1, 2020
(Exhibit #4)